



INDIAN INSTITUTE OF TECHNOLOGY BOMBAY
ESTATE OFFICE
NOTICE INVITING TENDER

Telephone No. 022 2576-4060, 022-2159-6922 email id drestate@iitb.ac.in

IIT Bombay invites digitally signed Technical Bid & Financial Bid for following work from the contractors having **similar** experience in Central Government Departments / State Government Departments / Central or State Autonomous Bodies / State or Central Public Sector Undertakings & Large Private Organizations. The detail of work is given below:

Sr. No.	Name of Work	Estimated Cost (In Rs.)	EMD (Rs.)	RFX	Duration of contract
1	Development of area in front of the old CSE Building for Car Parking. EO/A/WORKSHOP/WKS-62/26-27	Rs 12,29,973/- Incl.18% GST	Rs.24,000/-	610003067	03 MONTHS

Intending bidders need to register themselves on the IIT Bombay portal i.e. <https://portal.iitb.ac.in/vrp/index.jsp> to get User ID and Password. Please visit https://portal.iitb.ac.in/vrp/vrp_srm_docs.jsp for configuration process and user manual. For queries regarding vendor registration, and configuration process please contact on 022 - 2159 3001 (MDM Help-desk).

All tender documents, forms, etc are available online on <https://www.iitb.ac.in/resources/vendors-tenders> and Central Public Procurement Portal (CPPP) e-tender publishing portal of the Government of India.

Date and time of uploading of tender documents are from 23.06.2026 to 15.07.2026 till 11:15 a.m. Date of opening of Technical Bid will be 15.07.2026 at 11.30 a.m. and Financial Bid 22.07.2026 (Tentative).

All contractors/agencies should submit technical bid with the following documents, failing to which their tender will be summarily rejected from the tendering process:

1) **i.** Experience of having successfully completed works during the last 7 years ending last day of the month previous to the one in which applications are invited :

Three similar completed works costing not less than the amount equal to **40%** of estimated cost put to tender,

OR

Two similar completed works, costing not less than the amount equal to **50%** of the estimated cost put to tender

Or

One similar completed work of aggregate cost not less than the amount equal to **80%** of the estimated cost.

ii. One completed work of any nature (either part of (i) or a separate one) costing not less than the amount equal to **40%** of the estimated cost put to tender with some Central Government Departments / State Government Departments / State or Central Autonomous Bodies / State or Central Public Sector undertakings.

2) Upload a copy of the information in respect of manpower/mandays for above said work must be given in undertaking with official signature and seal/stamp, otherwise tender will be rejected.

3) P. F. registration certificate.

4) P. F. challans of last 12months.

5) ESIC registration certificate and copies of ESIC challans of the last 12 months (as per the labourers engaged during a particular month). Contractor name should be mentioned in the challans else the agency will be disqualified. OR Contractors' all risks insurance (CAR policy)

6) PAN card.

7) GST registration certificate.

8) Income Tax Return for **assessment year** i.e. of **2023-24, 2024-25 & 2025-26**.

9) List of Equipment's, Machinery, Tools.

10) List of Technical Staff with copies of their Degree/diploma certificate.

11) **Submit** DD/FDR/BG of Rs. 24,000/- in the name of "The Registrar, IIT Bombay" **before the opening of Technical Bid.** Contractors are also requested to upload a scanned copy of it to the online Tendering portal.

12) Power of Attorney, if any.

13) Proof of Constitution: An affidavit in case of Sole Proprietorship, Partnership Deed in case of Partnership Firm, Article of Association in case of Private / Public Limited Companies.

14) **Litigation history** of the agency is required to be upload along with the application. A tender would not be awarded if any inquiry proceeding / criminal case is found pending against the agency. If there is no enquiry then undertaking has to be uploaded in the format given.

15) Bank Solvency certificate 40% of estimated amount issued within one year from any Nationalized / Schedule Bank from the date of publishing of Tender.

16) Detail statement for work completed, work in hand including balance commitment of work should be enclosed for last three year commencing from 1st April and ended with 31st March and contractor should upload his details as per **Annexure 'A'** format with support of xerox copies of work order and work completion certificates, otherwise the bid capacity will not be calculated and his technical bid will be summarily rejected.

Terms & Conditions :

The documents listed below from Sr. No. 1 to 16 is mandatory for qualification in the technical bid evaluation process.

Select 'N5' tax code for 18% GST and upload all the above mentioned documents in "C folder" of online SRM tendering portal.

The work will be executed with lowest bidder as per the terms and conditions of work order and tender documents signed by the lowest bidder.

The validity of the bids will be valid for 6 months from the date of opening of tender.

No work will be subletted to third party. If found payment of final bill will not be processed and the contractor's name will removed from the enlistment without giving him further notice.

The rates is prepared from CPWD DSR 2023 & Rate Analysis.

Contractors are strictly prohibited from engaging in any correspondence related to tender documents with anyone other than the Tender Section. Any violation will result in disqualification from all future tenders.

No queries will be entertained within 24 hours prior to the opening of the tender. We kindly request all contractors to upload their quotations well in advance of the submission deadline to ensure a smooth and timely process.

IIT Bombay reserve its rights to reject any or all tenders without assigning any reason and without any reference. IIT Bombay reserves the right to request a detailed justification of the quoted rates from the lowest bidder, if deemed necessary by the Engineer-in-Charge. Should the justification provided by the bidder be considered unsatisfactory or unsubstantiated, the Engineer-in-Charge shall have full authority to reject the bid, irrespective of it being the lowest.


Superintending Engineer (I/C)
Date: 19/6 2016

DECLARATION

- (a) We are not involved in any litigation that may have an impact of affecting or compromising the works as required under this tender.
- (b) We are not black-listed by any Central/State Government/Public Sector Undertaking in India.
- (c) We hereby confirm and declare that M/s [Company Name] does not have any Litigation / Arbitration History with any Government department, Public Sector Undertaking (PSU), or Private Sector agency for works executed during the **last 5 years**.
- (d) I/we undertake that the documents submitted are genuine/authentic and nothing material has been concealed therefrom and that I/we are not debarred by any Government organization and are competent to have the contract. I/we understand that the contract is liable to be cancelled, if found to be having obtained, through fraudulent means/concealment of information.

(Signature of Authorized Signatory)

Name of the bidder:
Complete Address:

Address (Works), if

any: Contact Nos.

INDEX SHEET

Sr. No.	Content	Page No. From - To
1	Experience of having successfully completed works during the last 7 years ending last day of the month previous to the one in which applications are invited : Three similar completed works costing not less than the amount equal to 40% of estimated cost put to tender, OR Two similar completed works, costing not less than the amount equal to 50% of the estimated cost put to tender Or One similar completed work of aggregate cost not less than the amount equal to 80% of the estimated cost.	
2	Submit a copy of the information in respect of manpower/mandays for above said work must be given in undertaking with official signature and seal/stamp.	
3	Bank Solvency certificate 40% of estimated amount issued within one year from any Nationalized / Schedule Bank from the date of publishing of Tender.	
4	P. F. registration certificate.	
5	P. F. challans of last 12months.	
6	ESIC registration certificate and copies of ESIC challans of the last 12 months (as per the labourers engaged during a particular month).Contractor name should be mentioned in the challans else the agency will be disqualified.ORContractors' all risks insurance (CAR policy)	
7	PAN card.	
8	GST Registration certificate	
9	Income Tax Return for assessment year i.e. of 2023-24 ,2024-25 & 2025-26.	
10	List of Equipment's, Machinery, Tools.	
11	List of Technical Staff with copies of their Degree/diploma certificate.	
12	Earnest Money Deposit	
13	Power of Attorney, if any.	
14	Proof of Constitution: An affidavit in case of Sole Proprietorship, Partnership Deed in case of Partnership Firm, Article of Association in case of Private / Public Limited Companies.	
15	Litigation history of the agency is required to be submitted along with the application. A tender would not be awarded if any inquiry proceeding / criminal case is found pending against the agency.If there is no enquiry then undertaking has to be submitted in the format given.	
16	Annexure 'A'	
17		
18		

Signature & stamp of the Contractor

TO BE UPLOADED ON SRM TENDERING PORTAL WITH FINANCIAL BID

**ANNEXURE 'A' (FORMAT)
TECHNICAL BID**

File No. : EO/A/WORKSHOP/WKS-62/26-27

Name of Work : Development of area in front of the Old CSE Building for car parking.

Name of the Contractor -----

Sr. No.	Name of Client	Name of Works	2022-23 (In Lakhs)	2023-2024 (In Lakhs)	2024-2025 (In Lakhs)	2025-2026 (In Lakhs)	
						Completed	Balance
			-	-	-	-	-
			-	-	-	-	-
Total Amount (In Lakhs)			-	-	-	-	-

Note : Contractor must submit his details as per Annexure 'A' with declaration stating that **he is possessing all the original copies of work orders and experience certificates, it will be produced as and when required to IIT Bombay.** However, if it is found false at later stage, the contractor will be debarred or blacklisted. Whereas, if information is not submitted as per Annexure 'A' format his bid capacity will not be calculated and his tender will be summarily rejected.

6 
22/6/26
Superintending Engineer (I/C)


19/6/26
19/6/26

Signature of Contractor
Name & Address in full

WORKS UNDERTAKING

EO/A/WORKSHOP/WKS-62/26-27

To,
Superintending Engineer (I/C)
Indian Institute of Technology,
Powai, Mumbai – 400 076.

Sub : Development of area in front of the Old CSE Building for car parking.

Dear Sir,

We are hereby quoting all the rates for the attached schedule of short tender of the above mentioned job.

We hereby accept & signed all the General Terms and Conditions and special Conditions of Contract.

The work will be completed within specified time limit of 3 months as mentioned in the notice inviting for short tenders.

The following information is required to be provided.

I / We agree to keep the tender open for One Hundred and Eighty (180) days from the due date of its opening / One Hundred and Eighty days from the date of opening of financial bid in case tenders are invited on 2/3 envelope system and not to make any modification in its terms and conditions.

	Male	Female
No. of Unskilled casual labour to be required per day.		
No. of Skilled casual labour to be required per day.		
Total Mandays required for completion of work.		

Thanking you,

Yours faithfully,

Signature of the Contractor
With official Seal / Stamp of the firm

INDIAN INSTITUTE OF TECHNOLOGY BOMBAY
POWAI, MUMBAI, MAHARASHTRA - 400 076

EO/A/WORKSHOP/WKS-62/26-27

ESTATE OFFICE

Name of work:- Development of area in front of the Old CSE Building for car parking.

Schedule of Work

Sr. No.	Description of work	Qty	Unit
1	Excavation for foundation, trenches, Roadway etc. in earth, soil of all types, sand, gravel, soft and hard murum, soft rock etc. including removing the excavated materials up to a distance of 50 meters beyond the site of work and lift up to 1.50 meters, stacking and spreading as directed preparing the bed for the foundation and necessary dewatering using pump, backfilling, ramming, watering, including shoring and strutting, providing necessary barricading around excavated area etc. complete.	43.00	m3
2	Dismantling plain cement concrete work including breaking concrete by chiselling, wedging etc., and stacking the debris upto a distance of 50 metres or spreading as directed.	2.00	m3
3	Pulling down stone masonry in cement mortar with plaster / pointing without dust nuisance including sorting out the stone chips and debris separately and stacking upto distance of 50 metres or spreading the debris as directed.	2.00	m3
4	Removing soling without dust nuisance including sorting out the stone chips and debris separately and stacking upto distance of 50 metres as directed.	1.00	m3
5	Laying dry trap / rubble stone soling of required thickness including hand packing and compacting in proper level all complete as directed by Engineer-in-charge.	36.00	m3
6	Providing second class burnt brick masonry with IS approved quality well burnt bricks having in cement mortar 1:6 in superstructure including striking joints, racking out joints, watering and scaffolding complete.	5.00	m3
7	Providing internal cement plaster 20mm thick in a single coat in cement mortar 1:4 without neeru finish to concrete or brick surfaces in all positions with the use of step ladder and curing complete.	39.00	m2
8	Providing and casting in position ready mixed or machine batched M-20 grade cement concrete (Min cement content 270Kg/Cum) for foundation, coping and bedding etc. as per approved excluding shuttering, including compaction, finishing, curing etc. including cost of admixtures in recommended proportions as per relevant IS code to accelerate/ retard setting of concrete, improve workability without impairing strength and durability as per direction of the Engineer-in-charge including casting cubes and testing.	2.00	m3
9	Providing uncoursed rubble masonry of trap stones in cement mortar 1:6 (Cement:sand/grit) including racking out joints when plastering is to be done, striking out joints, watering, including providing header stones @ 1 header per sqm. to the full thickness of wall, providing weep holes, with 100mm dia pvc pipes including collecting and transporting stone stacked in IITB Campus, cutting stones/ bouldres in piceses as per requirement, etc. complete as directed. (Payment of PVC pipe shall be paid seperately)	8.00	m3
10	Providing uncoursed rubble masonry (using IITB stones) of trap stones in cement mortar 1:6 (Cement:sand/grit) including racking out joints when plastering is to be done, striking out joints, watering and pointing with cement mortar 1:3 on outside exposed faces, including providing M-20 grade concrete block header @ 1 header per sqm. to the full thickness of wall, providing weep holes, with 100mm dia P.V.C pipes including collecting and transporting stone from various locations from IIT Campus upto working site, cutting stones/ bouldres in piceses as per requirement, scaffolding etc. complete as directed.	3.00	m3

11	Providing and laying in position machine batched and machine mixed design mix M-25 (1:1:2) grade cement concrete for all work up to plinth level for reinforced cement concrete work, including pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per direction of Engineer-in-charge including compacting, roughening the surface if special finish is to be provided, casting cubes and testing etc. completed as directed.	12.00	m3
12	Painting road surface marking with adequate nos of coats to give uniform finish with ready mixed road marking paint conforming to IS : 164, on bituminous surface / paver block in white/ yellow shade, including cleaning the surface of all dirt, scales, oil, grease and foreign material etc complete. (Two or more coats)	23.00	m2
13	Construction of granular sub-base, Grade-V having gradation as per MORTH table 400-1 (size range 75 mm to 0.425 mm) by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material using machinery to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge, collecting samples, testing as per section 900 of MORTH and submitting reports etc. completed as directed. (Note : The mix design with all relevant data to be submitted & prior approval is to be obtained from IIT Bombay. Compacted thickness will be taken for payment.)	54.00	m3
14	Providing and laying Lacquer finish coloured paver blocks in specified pattern 80 mm thick for floor and steps etc. with compressive strength not less than 45 N/sqmm over and including 50mm thick compacted bed of fine sand in specified decorative designs with blocks of different colour and pattern including filling the joints with fine sand and cleaning completed as directed.	269.00	m2
15	Taking out existing CC interlocking paver blocks from parking area, footpath, central verge etc. including removal of rubbish, disposal of unserviceable material upto 50 mtr distance. Stacking of serviceable material within 50 metre lead as per direction of Engineer-in-Charge.	83.00	m2
16	Laying old cement concrete interlocking paver blocks of any design/shape laid in required line, level, curvature, colour and pattern over and including 50 mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge. (Old CC paver blocks shall be supplied by the department free of cost).	83.00	m2
17	Dismantling burnt brick masonry (in cement mortar) with plaster including sorting out serviceable bricks and lowering down debris, stacking the same and debris separately upto a distance of 50 meters or spreading the debris as directed.	1.00	m3
18	Fabricating and fixing structural steel works supplied by Institute in rolled sections like joists, channels, angles, tees, hollow sections and any other required sections etc. as per detailed designs & drawings for supports, rafters, purlins, railing and any other work including fixing in position with connecting plates, braces and welding, riveting, bolting as necessary including painting, scaffolding etc. complete.	990.00	Kg
19	Providing and fabricating structural steel works in rolled sections like joists, channels, angles, tees, hollow sections and any other required sections etc. as per detailed designs & drawings for supports, rafters, purlins, railing, staircase and any other work including fixing in position with connecting plates, braces and welding, riveting, bolting as necessary including one coat of redoxide priming coat etc. complete as directed.	131.00	Kg
20	Providing and fixing precast RCC slab for drain cover and chamber cover of required size with M-25 grade concrete and reinforced with 10mm dia main steel bars (along shorter span) and 8mm. dia distribution bars (along longer span) at 100mm center to center including making steel form work, making temporary concrete platform for casting, compaction using surface vibrator, with two lifting hooks of 6mm dia / holes of 25mm dia finishing the surface with smooth cement finish curing, placing the precast slab in proper position etc. complete as directed.	0.50	m3

21	Providing and fixing 600mm x 600mm rectangular Heavy duty FRP grating covers with frame for inspection chamber / manhole / gulley trap/ over storm water drain and other required places manufactured by M/s.KK or IITB approved make including closing the gaps between frame and surface with cement mortar all complete as directed.	4.00	Nos
22	Providing and laying 100mm dia. P.V.C. pipes conforming to I.S. in trenches including proper slope, filling the joints using solvent cement etc. completed as directed.	15.00	Rmt
23	Providing and fixing factory made kerbstone of size 300 x 300 x 150 mm in M-25 grade of concrete using design mix minimum cement content as per IS 456 for the moderate exposure condition including P.C.C (1:2:4) 100mm thick bedding, fixing the kerb stone over P.C.C bedding and grouting the joints with 1:3 cement mortar to the required line, level, curing etc. complete (Rate excluding excavation) (length of finished kerb edging shall be measured for payment). (Precast C.C. kerb stone shall be approved by Engineer-in-charge).	21.00	Rmt
24	Providing and applying one coat of acrylic primer and two coats of exterior acrylic paint of approved colour & shade of IITB approved manufacturer i.e. Berger, Asian, Killick Nixon, Goodlass, Nerolac, ICI, Decocem and as per manufacturer's specification on old or new plastered surface over concrete / brickwork, stonework as per manufacturer's specification and cleaning the surface thoroughly with coir brush, watering the surface etc. complete including covering the floor, window glass with plastic sheet etc. all complete as directed by Engineer In-charge.	171.00	m2
25	Disposing debris, loose stones, boulders, concrete pieces broken etc. collected and stacked as directed including loading in trucks, transporting out of IIT Campus including obtaining approval from Government/ private land owners for disposing off on to their approved location. The contractor will be solely responsible for disposing debris out of campus and the debris are to be removed from site within 72 hours from stacking (30% voids will be deducted from actual measurement for debris, loose stones, boulders, concrete pieces).	20.00	m3
26	Removing excavated earth or debris including loading in trucks and conveying to approved dumping point in IITB campus unloading spreading etc. complete. 30% voids will be deducted in case of truck measurement.	5.00	m3

1) Note : This schedule of work is given for reference purpose only. Contractors are requested to quote your rates online in financial bid.

2) If you will engage labourer 20 or more any day, you have to get labour licence as per contract Regulation & Abolition Act 1970 Rule 1971, and also, you have to keep all such record for inspection to the Principal Employer. If you will engage labour up to 10 Nos. per day, you have to file returns after completion of work as per Building & Construction Act to the Office of Regional Labour Commissioner (Central), Sion, Mumbai.


3) This work is to be executed as per the clauses mentioned in the tender document signed by you. In addition to the existing safety clause of the tender document a penalty of Rs.5,000/- per case will be recovered from the bills of the particular works, in case any such safety violations are noticed.

4) 01% amount will be deducted from the bills for safety related measures which will be reimburse along with the final bill.

5) Taxes as per government notification time to time.

6) Contractor must pay GST Taxes to concern authority within 30 days time limit after receipt of payment from IIT Bombay & said record must be submitted to IIT Bombay Accounts Section, otherwise action will be taken as deemed fit.

7) If any malpractices / fraud / negligent professional behaviour or any discrepancy / inconsistency / disparity / deviation / disagreement / dissimilarity / mismatch noticed, their contract will be terminated by issuing one month notice by following legal procedure and will be blacklisted and informed to all Government Authorities and Organisations.


 Superintending Engineer (I/C)

 22/6/26